

### Scope of Work Summary

The ROW preparation will be carried out with standard utility practices and procedures and will involve the clearing of all vegetation that exceeds 2 m at maturity. Access will be similar to resource road access typical in the forest sector. Work also includes installation of culverts, short span and long span bridges within the Right of Way.

This includes chainage 211+300 km to 360+400 km (approximately) on the island of Newfoundland.