

Scope of Work Summary

The Construction of North and South Dams consists of the construction of the North Dam (Roller Compacted Concrete (RCC) overflow and the South Rock Fill Dam construction and removal of Cofferdams, including the main upstream Cofferdam for river diversion. Construction and removal of Cofferdams, construction and removal of a temporary access bridge over spillway approach channel as well as excavation of Tailrace Rock Plug. The package also includes foundation preparation, exploitation of sources of materials (borrow pits and stockpile areas), production of aggregates, Conventional Vibrated Concrete (CVC) and (RCC) as well as the completion of final grading of permanent access roads and the powerhouse parking area.