

CH0030 Turbines and Generators

1. Package Description

Scope of Work Summary:

The scope of work consist of the design, fabrication, shop testing, delivery, installation, field testing, commissioning and guarantee of four (4) turbine-generator units with a capacity of 229 MVA under a rated net head of 35 m, 0.9 p.f. and 15 kV. Each unit shall be complete with speed governor, static excitation system, protection and control system and monitoring system.