

**CT0327-013 HVdc Clearing and Access - Section 1 (Blocks Nos. 4, 5 and 6 partial)**

The ROW preparation will be carried out with standard utility practices and procedures and will involve the clearing of all vegetation that exceeds 2 m at maturity. Main Access roads shall be constructed under this agreement and will be similar to resource road access typical in the forest sector. Work also includes installation of culverts, short span and long span bridges within the Right of Way.

This includes chainage 143+750 km to 328+000 km (approximately) in Labrador.